



Celsius

Webinar

1 September 2016






Damien Coyle

Project Manager






Celsius



Introduction

Project overview



Progress and next steps

Questions & answers

Webinar format



30 minutes presentation



20 minutes
questions & answers



Submit written questions
online during the webinar

Q&A panel



electricity
north west

Bringing energy to your door



Damien Coyle
Innovation
Project
Manager



Paul Turner
Innovation
Delivery
Manager



Kate Quigley
Innovation
Customer
Manager


Our smart grid development



electricity
north west

Bringing energy to your door

Leading work on developing smart solutions



Deliver value
from existing
assets



Customer choice



Five flagship products (second tier/NIC) £42 million

C2C

SMART STREET


Celsius

CLASS

RESPOND



Awarded: 9 December 2015



 Investment	£5.5 million	Up to £583m across GB by 2050	 Financial benefits
-----------------------	---------------------	--------------------------------------	-------------------------------



Partners and roles on project



electricity
north west

Bringing energy to your door

ASH
CREATIVE WIRELESS ELECTRONICS

Supply complete retrofit monitoring solution.

Provide ongoing support throughout installation, commissioning and operation of the retrofit thermal monitoring workstream

RICARDO

Analyse trial data.
Develop methodology to understand relationship between asset temperature, load characteristics and surrounding environment

Determine impact of cooling technologies
Develop tool and spec for low cost temperature sensor
Recommendations for BAU rollout

UK Power Networks
Delivering your electricity

Work with Ricardo-AEA and Electricity North West to develop site selection methodology, installation plan and guide for future retrofit thermal monitoring solution

Participate in evaluation and selection of retrofit cooling techniques

Impact Research



Lead the customer survey engagement.

UNIVERSITY OF
Southampton

Peer review of the analysis methodology of the retrofit temperature sensor part of the project

An investigative study on the impact of Celsius on the lifetime health of network assets

The problem




Objective is to maximise power through transformer

Assets have nominal thermal rating
Ratings = °C
Ratings \neq amps


Diverse range of environments
Small changes in environmental factors can result in very different actual ratings

Assumed thermal ratings can lead to capacity being under-utilised or unnecessary risk


Celsius as part of the smart future



Step 1: Fit thermal monitoring




Step 2: Retrofit cooling





Thermal analysis (step 1)



Internal asset
temperature




Thermal
coefficient



External asset
temperature

Thermal flow study (steps 1 & 2)



Research into heat and air flows for
optimal substation design

Asset health study (steps 1 & 2)




Examines effects of increased load
and cooling techniques on assets

Monitoring site selection and timescales



520 substations

Enough substations to represent 80% of GB substation population



100 cooling technique sites

Subset of 520 substations – enough sites to adequately trial all techniques



Four year project

To enable trials to take place during all seasons and to trial all cooling techniques

Site selection map





Site selection – rural and urban




electricity
north west

Bringing energy to your door



Site selection



Commissioning app



CELSIUS: Site List Help

IN PROGRESS

DENE RD
ID: 171526
Location: DIDSBURY In progress >
Monitoring: Type 1
Region: Manchester (South)

Ash Wireless
ID: 1
Location: Southampton In progress >
Monitoring: Type 1
Region: Manchester (South)

**TOWNEND FM M6
SUPPLIES_11**
ID: 660360 In progress >
Location: Lowther

< >

CELSIUS: Hubs and Sensors Help

Sensor Positions

144409FA9D0E
Component: Transformer
Type: Single Temperature Sensor----- >
Position: Top Oil Temperature -
Face 1

0818D700CF9B
Component: Transformer
Type: Single Temperature Sensor----- >
Position: Bottom Oil Temperature -
Face 1

0F15832CF100:0
Component: LV Board ----- >
Type: Hex voltage flying lead
Position: Voltage Phase 1

< >

Celsius technology



electricity
north west

Bringing energy to your door

Hub




Wireless sensor



Celsius technology – trial fit




LV board with three sensors





Transformer singles





Ventilation








Transformer



Traditional reinforcement v Celsius



	Traditional	Celsius
	Traditional replacement of ground-mounted transformer is expensive	Low cost options to release capacity as and when required
	Complex and time-consuming	Simple and quick to deploy
	Highly disruptive	Minimal or no disruption to customers

Customer engagement



electricity
north west

Bringing energy to your door

Customers in the Celsius trial areas will find the implementation of innovative retrofit cooling techniques as acceptable as traditional reinforcement

Customers who are educated as to the need for and benefits of Celsius are significantly more likely to find it acceptable

Customer engagement



Customers in the Celsius trial areas will find the implementation of innovative retrofit cooling techniques as acceptable as traditional reinforcement

Customers who are educated as to the need for and benefits of Celsius are significantly more likely to find it acceptable



Customer engagement plan



Baseline survey



Test survey



Focus groups

Website



Video/
podcasts




Customer mailing



Social media



Progress and next steps



Knowledge sharing and dissemination

Questions & answers



electricity
north west

Bringing energy to your door



Damien Coyle
Innovation
Project
Manager



Paul Turner
Innovation
Delivery
Manager



Kate Quigley
Innovation
Customer
Manager



Submit written questions online

Post event feedback



	Strongly disagree	Slightly disagree	Neutral	Slightly agree	Strongly agree
Today's webinar was successful in raising my understanding of the Celsius project				57%	43%
Webinars are suitable channels for communicating innovation project outcomes and are more convenient than attending an event in person.				14%	86%
I will take part in other webinars organised by Electricity North West to discuss low carbon projects.				29%	71%
Do you have any comments or suggestions about how we could have improved today's webinar?	<p>1. Have you considered increasing noise levels by installing fans? 2. Have you considered Air handling units? 3. The project may release some capacity in the transformer but that suggest cables will be stressed by increased load. Will there be any monitoring of thermal impact on cables. 4. Experience suggests temperature raise in the core of transformer can not be monitored by top and bottom sensors. How will you monitor that?</p>				

For more information



electricity
north west

Bringing energy to your door



www.enwl.co.uk/celsius



futurenetworks@enwl.co.uk



0800 195 4141



[@ElecNW_News](https://twitter.com/ElecNW_News)



[linkedin.com/company/electricity-north-west](https://www.linkedin.com/company/electricity-north-west)



[facebook.com/ElectricityNorthWest](https://www.facebook.com/ElectricityNorthWest)



[youtube.com/ElectricityNorthWest](https://www.youtube.com/ElectricityNorthWest)

Please contact us if you have any questions or would like to arrange a one-to-one briefing about our innovation projects